SPL-202206-0013 Dated 29-06-2022

Saraswaty Press Limited invites Sealed offer for Supply, Erection, Testing & Commissioning of Fire Sprinkler and Fire Detection system from Experienced Vendors who are registered with the relevant statutory authorities e.g. GST, PAN, PF & ESI for the below mentioned jobs in Unit II, 5/5 B.T. Road, Kolkata-700056.

Sl.No	Description	Qty	Unit	Unit Rate (Rs)	Amount (Rs)					
A	Sprinkler & Fire detection network inside the Hedilberg									
1	Supply & Installation of mild steel heavy pipe with painting									
а	150 mm	2	mtr							
b	50 mm	18	mtr							
С	25 mm	6	mtr							
2	ISI marked 50 mm butterfly valve PN 1.6 Make- Kitz	1	no							
3	ISI marked 50 mm non return valve PN 1.6 Make- Kitz	1	no							
4	Side wall sprinkler 68 degree Make - HD / Newage	7	no							
5	Structural Steel & fittings	20	kg							
6	Heat detector	3	no							
7	Hooter	1	no							
8	MCP	1	no							
9	Control relay module Make - Morley	1	no							
10	2 C x 1.5 sq mm ISI marked armoured cable Make - Polycab	125	mtr							
11	SMPS input voltage 230 volts AC .Output voltage 24 volt DC. Amp 5 Make - Micropower	1	no							
12	Charges for testing & commissioning	1	no							
	Total amount for A in Rs									

a	Supply & Installation of mild steel heavy pipe with painting 80 mm										
	80 mm		Supply & Installation of mild steel heavy pipe with painting								
b		42	mtr								
	65 mm	6	mtr								
с	40 mm	54	mtr								
d	25 mm	18	mtr								
2	ISI marked 80 mm butterfly valve PN 1.6 Make- Kitz	1	no								
3	ISI marked 80 mm non return valve PN 1.6 Make- Kitz	1	no								
4	Structural Steel & fittings	40	kg								
5	Pendent sprinkler 68 degree Make - HD / Newage	18	no								
6	80 mm galvanised steel pipe- heavy for pilon support	36	mtr								
	Pedestal civil foundation ($400 \ x \ 400 \ x500 \ mm$) for internal pilon support	16	no								
8	Heat detector	6	no								
9	Hooter	1	no								
10	MCP	1	no								
11	Control relay module Make - Morley	1	no								
12	2 C x 1.5 sq mm ISI marked armoured cable Make - Polycab	125	mtr								
	SMPS input voltage 230 volts AC .Output voltage 24 volt DC . Amp 5 Make - Micropower	1	no								
14	Charges for testing & commissioning	1	no								
	Total amount for B in Rs										
С	Pump House work - Hydrant & Sprinkler system by pass connection										
	Supply & fixing ISI marked 150 mm butterfly valve PN 1.6 Make-Kitz	2	no								
	Total amount for C in Rs										

Plus GST as applicable.

Offer may be sent within 18/07/2022 within 2 P.m. to the Purchase Committee, Saraswaty Press Limited, 11, B.T.Road, Kolkata- 700056, Phone 2564-7469. The Company reserves the right to accept, negotiate or reject any or all offer with any vendor at its own discretion.