

Tender No. SPL-2021 07-0007 DT-13-07-2021

Saraswasty Press Ltd. invites sealed offer from experienced civil contractor who are technically capable, experienced, and financially sound and having experiences of timely execution of proportionate volume of work of similar nature, for construction of 4.5 Lac litre capacity Fire water reservoir tank at SPL unit 3, Badu Road, Madhyamgram, Kolkata-700128. Construction details and measurements are provided in the attached list.

A bidder shall have to furnish the following documents to meet the eligibility criteria:

- GSTN Registration certificate.
- Trade License
- P.Tax and its latest challan
- Pan Card
- Audited Balance Sheet & Profit & Loss Account for the 2(two) financial years (2018-2019 and 2019-2020).
- Two years (2018-2019 and 2019-2020) Income tax Return.
- Certificate of enlistment under PF & ESIC Act.

Rate should be quoted in sealed envelope with all required documents and filled up annexed sheet with applicable GST. Last date of submission on 29<sup>th</sup> July,2021 by 2 pm to the Purchase Committee, Sarasawaty Press Limited, 11, B. T.Road, Kolkata-700056, Phone: 2564-7469. The company reserves the right to accept, negotiate or reject any or all offer with any vendor at its own discretion.

**Annexure-1**

<b>Sl. No.</b>	<b>Item Description</b>	<b>Unit (approx)</b>	<b>Unit of Measurement</b>	<b>Rate</b>	<b>Total Amount Without GST</b>
1	Earthwork in excavation for foundation in all sorts of soil for a depth of excavation not exceeding 2 m including removing, spreading or stacking the spoils within a lead of 75 m as directed. The item includes necessary trimming of the sides, Levelling, dressing and ramming the bottom boiling out water etc as required complete.	670	Cubic meter		
2	Material for Supply of Silver Sand for Foundation/ plinth filling all complete including watering, compacting etc.	75	Cubic meter		
3	Labour for Supply of Silver Sand for Foundation/ plinth filling all complete including watering, compacting etc.	75	Cubic meter		
4	Materials for providing Brick Flat Soling with 250 X 125 X 75 thk bricks with interstices filled up with Silver Sand/ Earth Powder all complete.	250	Square meter		
5	Labour for providing Brick Flat Soling with 250 X 125 X 75 thk bricks with interstices filled up with Silver Sand/ Earth Powder all complete.	250	Square meter		
6	Materials for Providing and laying plain cement concrete (1 : 2 :4) with 20 mm down stonechips including shuttering, curing etc in foundation.	20	Cubic meter		
7	Labour for Providing and laying plain cement concrete (1 : 2 :4) with 20 mm down stonechips including shuttering, curing etc in foundation.	20	Cubic meter		
8	Material for supplying, cutting, bending, binding and fixing in position with 16 gauge black arrealed wire steel Reinforcement of grade Fe-415	7250	Kg		
9	Labour for supplying, cutting, bending, binding and fixing in position with 16 gauge black arrealed wire steel Reinforcement of grade Fe-415	7250	Kg		

<b>Sl. No.</b>	<b>Item Description</b>	<b>Unit (approx)</b>	<b>Unit of Measurement</b>	<b>Rate</b>	<b>Total Amount Without GST</b>
10	Materials for providing and laying reinforced cement concrete (1: 1.5 : 3) with 20 mm down stonechips excluding reinforcement but including shuttering, curing, finishing smooth all complete in foundation upto Plinth Level	70	Cubic meter		
11	Labour for providing and laying reinforced cement concrete (1: 1.5 : 3) with 20 mm down stonechips excluding reinforcement but including shuttering, curing, finishing smooth all complete in foundation upto Plinth Level	70	Cubic meter		
12	Materials for Providing cement brick work (1 : 4) at 1.0 m below and 3.0 m above ground level all complete including curing.	40	Cubic meter		
13	Labour for Providing cement brick work (1 : 4) at 1.0 m below and 3.0 m above ground level all complete including curing	40	Cubic meter		
14	Materials for providing 10 mm thk cement sand plaster (1:4) on ceiling all complete including curing but excluding scaffolding	400	Square meter		
15	Labour for providing 10 mm thk cement sand plaster (1:4) on ceiling all complete including curing but excluding scaffolding	400	Square meter		
<b>Total</b>					

Plus GST as applicable.